

6 JOHN STREET
PICTON, ON
TREE INVENTORY

CONTACT:

ArbreCareTree Service
P.O. Box 35057
Kingston, ON K7L 5S5
613-634-6341
arbrecare@gmail.com

LOCATION:

6 John Street, Picton, ON

LIST OF TREES ON SITE:

On August 9, 2023, ArbreCare Tree Service completed a tree inventory at 6 John Street.

Trees on site:

1. Manitoba maple (*Acer negundo*) 82 cm DBH - poor condition
2. Manitoba maple (*Acer negundo*) 80,106,86 cm DBH – poor condition
3. Norway maple (*Acer platanoides*) 21 cm DBH – moderate condition
4. Norway maple (*Acer platanonides*) 52 cm DBH – moderate condition, large crack in trunk

TREE PROTECTION:

If there are any trees to be retained they need to be protected by a Tree Protection Zone. The Tree Protection Zone (TPZ) is the area around the trees that will have no grading or construction activity occur. The area will be fenced off and there will be no storage of materials of any kind, no parking or moving of vehicles, and no disturbance of the soil or grade. As well there will not be:

No disturbance or alteration of the existing grade of any kind
No addition of fill, excavating or scraping to change the grade
No storage of building materials or equipment
No disposal of contaminants or liquids
No movement of vehicles or equipment

Protection Measures

All supports and bracing will be used to safely secure the barrier should be located outside the TPZ. All supports and bracing will minimize damage to roots.

Tree Protection Barriers

Tree protection barriers shall be installed according to the following guidelines:

A 2.4 metre (8 ft.) high plywood clad hoarding is the most preferred barrier. Other cladding can be considered. The barrier can be lowered around branches lower than 2.4 metres (8 ft.). Within a City road allowance, where visibility is a consideration, 1.2 metre (4 ft.) high orange plastic web snow fencing on a 2" x 4" frame should be used.

All supports and bracing used to safely secure the barrier should be located outside the TPZ. All supports and bracing should minimize damage to roots.

Where some fill must be temporarily located near the TPZ, a plywood barrier must be used to ensure no material enters the TPZ.

If there is any digging within this Tree Protection Zone an arborist will be on site to supervise.

Pruning: If limbs need to be removed to accommodate construction work, they will be removed carefully in accordance with accepted arboricultural practices.

Root pruning: Where the root system of any tree is exposed directly adjacent to or are damaged by construction work, they will be trimmed neatly, and the area backfilled with appropriate material to prevent desecration.

Trunk barrier: There will be no trunk barrier because of the property line fence and the plywood cribbing will be in place.

